

## Product Improvement Plan

Prepared for:  
**Doubletree by Hilton**  
San Pedro, CA  
(InnCode: LGBSP, Facility ID:41338)

2800 Via Cabrillo Marina, San Pedro, California, United States  
To be relicensed as a Doubletree by Hilton



Inspection Date: Jun-20-2012  
FINAL PIP REVISION DATE : Feb-08-2013 by Ron Wojcik  
**Brand Management Approval**  
Final PIP Approval Date : Feb-08-2013

Final FLA PIP Approval Signature :

PIP Contact  
Ron Wojcik  
Email: ron.wojcik@hilton.com  
Phone: 919-720-4596

Printed On: Feb-08-2013



CONRAD  
WORLDWIDE HOTELS & RESORTS



Hilton  
Garden Inn



HOMewood  
SUITES  
BY HILTON



Hilton  
Grand Vacations

### Property Information

Open Date:	2006-08-15
Last Renovation:	2012: Pre-function area carpet and vinyl wall covering
Parking:	Surface: Asphalt
Pool (indoor or outdoor):	Outdoor
Whirlpool:	Outdoor
Hotel Van:	Courtesy Shuttle (2)
Number Floors:	3
Food Service Facilities:	Marina Bar & Grill
Meeting Space/total size:	16,000 SF consisting of one ballroom, seven meeting rooms and two boardrooms
Business Center:	Lobby desk
Exercise Room/Size:	Yes (Preco; 16'-0" x 24'-0")
Other Recreation:	Pool table (lobby)
Retail Outlets:	Gift Shop
Guest Laundry:	No
Number Of Guest Rooms:	226
Guest Room Size:	12'-6" x 15'-6" (Typical King)
Guest Room Mix:	
Typical King:	121
Typical D/D:	1
Typical Q/Q:	85
Single Queen:	6
King Suite:	10
King Junior Suite:	3
Guest Bathroom:	
Size:	6'-0" x 8'-0"
Door Width:	32" (pocket door)
Tub Surround:	4" tile, Roll-in shower available
Floor:	8" tile
Vanity:	Straight vanity (no furniture base) with stone top/apron and under-mount china bowl
Water Closet:	Tank-type with elongated bowl and closed-front seat
HVAC System:	
100% Makeup Air:	No
Public Areas:	Packaged units
Guestrooms:	Split system; Wall mounted thermostats in all guestrooms (about half are digital)
Elevators:	Three guest elevators (one at ballroom); two service elevators (one at ballroom)
High Speed Internet (wired or wireless):	
Public Areas:	Wireless (Stay Connected)
Meeting Space:	Wireless/Wired (Stay Connected)
Guestrooms:	Wired (Stay Connected)
Telephone System:	Two lines and two handsets in each room; Integrated with OnQ; Self-programmable wake-up

## EXHIBIT A

**PLEASE NOTE: Key information about the terms and effectiveness of this Property Improvement Plan is set out at the end of the document.**

<b>General</b>			
#	Active Date	Scope of Work	Finish Date
<b>General</b>			
1		Notice to owner: All hotels must comply with applicable local, state, and federal accessibility requirements. This PIP does not necessarily include any work that may be required for compliance with Title III of the Americans with Disabilities Act (ADA). In addition, if a Franchise Agreement or a Management Agreement for a hotel constructed for first occupancy after January 26th 1993 is executed after March 30th 2011, Hilton Worldwide will require the owner to conduct a self-survey (provided by Hilton Worldwide) of the hotel's guestrooms and parking for compliance with ADA Title III requirements. Any areas of non-compliance will need to be addressed within five to seven years (depending on the item in question) as a condition of the franchise or management agreement.	Per Brand Standards
<b>General/Accessibility/Fire Safety Requirements</b>			
#	Active Date	Scope of Work	Finish Date
<b>General</b>			
2		Design Approval Process - All scope of work identified in this PIP document requires a design review by DoubleTree by Hilton Brand Management. All architectural plans, design schemes, material specifications and professionally prepared color boards/renderings, must be submitted for formal review, comments and written approval prior to commencing work. See the DoubleTree by Hilton Design & Construction Manual for detailed specifications on all areas of this PIP document. All architectural and design plans submittals are required to be compiled by a licensed Architectural and/or licensed Interior Design Firm. Send materials to: Director of Design, DoubleTree by Hilton Global Design.	12 Months
<b>Basic Standards Issues</b>			
#	Active Date	Scope of Work	Finish Date
<b>Structure</b>			
3		General Design & Construction - Per DoubleTree by Hilton Design and Construction standards, hotels may not install tile over tile in any area of the hotel. The standards require the old tile to be completely removed and new tile installed. Hotels may not install wall vinyl over existing wall vinyl in any area of the hotel. The standards require the old wall vinyl to be completely removed and the new wall vinyl installed. The DoubleTree by Hilton brand and Quality Assurance will strictly enforce the above items.	12 Months
<b>Technology</b>			
4		High Speed Internet Access - Every DoubleTree by Hilton hotel must participate in the Hilton Worldwide High Speed Internet Access (HSIA) program "Stay Connected™". Complimentary wireless HSIA must be available in the lobby, prominent guest dining areas, lounge / bar, executive lounge and Connectivity Stations / Business Center. In addition, all Gold/Diamond members of Hilton HHonors must receive complimentary high-speed Internet access in the guest room (wired and wireless if available) for the Member and one additional guest or device."	12 Months
<b>Signage</b>			
#	Active Date	Scope of Work	Finish Date
<b>Interior Signage</b>			
5		Interior Signage - Remove all signage from doors (signage must be mounted on the wall adjacent to the strike side of the door).	18 Months

<b>Site</b>			
#	Active Date	Scope of Work	Finish Date
<b>Landscaping</b>			
6		Landscaping - Renovate the landscaping, removing all dead/dying plant material around the perimeter of the parking lot/parking lot islands and trimming back all overgrown plants/grass. Replace all missing landscaping near the retail outlet.	12 Months
<b>Parking</b>			
7		Parking - Repair and repave all damaged/cracked parking and drive areas. Re-seal and re-stripe all parking and drive areas. Parking lot striping must be white, except where other colors are required for fire lanes, no parking zones, and accessibility. Repaint any curbing that is currently painted.	12 Months
8		Parking - Replace all damaged/crumbling concrete wheel stops.	12 Months
9		Parking - Replace all cracked, broken or heaving sections of concrete sidewalk (see especially along the front of the building and the Madeo Ballroom courtyard). Restore the faded decorative finish of all sidewalks (where applied).	12 Months
10		Dumpster/Storage Enclosures - Remove the chain link fencing around the dumpsters and around the storage area by the tennis courts. Install a permanent structure or structures matching the finishes of the main building. Remove all storage trailers.	12 Months
11		Service Area - Repaint the gates at the service area adjacent to the pool (repairs mismatched).	12 Months
<b>Building Exterior</b>			
#	Active Date	Scope of Work	Finish Date
<b>Facade</b>			
12		Facade - Replace all damaged fabric awnings (see especially at the Bosanka/Marina Rooms). New awnings must exactly match the existing awnings. If the awnings cannot be matched, replacement of all awnings will be required.	12 Months
13		Facade - Repair and repaint the rusted access panel and ventilation grill at the south side of the Madeo Building. Replace the damaged covered service area doors at the east side of the Madeo building.	12 Months
<b>Porte Cochere</b>			
14		Porte Cochere - Restore the wood finish of the chipped/scuffed bell stand to a "like new" condition. Replace all missing/damaged trim pieces.	12 Months
15		Porte Cochere - Remove all extension cords running from the porte cochere service lighting to the rope lighting around the palm trees. Wiring and/or wiring conduit must be concealed from guest view in all public areas of the hotel (to include the Madeo Room courtyard).	12 Months
<b>Doors</b>			
16		Exterior Doors - Professionally restore the finish of all secondary entrance doors and door frames to a "like new" condition using an electrostatic paint process (to include restaurant area doors, meeting room doors, entry gates at pool, etc.). Replace all worn/scuffed door hardware.	12 Months
<b>Windows</b>			
17		Windows - Restore the finish of all faded window frames to a "like new" condition (see especially at the back side of the Terrasini Room, Food & Beverage office, Engineering office, etc.). Remove all oxidation, clean and re-caulk exterior frames and trim. If painting of the window frames is required, it must be professionally done using an electrostatic paint process.	12 Months
<b>Public Areas</b>			
#	Active Date	Scope of Work	Finish Date
<b>Entrance/Lobby/Registration Area</b>			

## EXHIBIT A

18		Lobby - Conduct a full renovation of the lobby space to include: restoration of the worn stone tile flooring; replacement of all carpet and carpet pad and the installation of new carpet, tile, natural stone, wood or other approved flooring; replacement of all pink stone base, trim and low wall caps; replacement of all soft seating; restoration of all wood occasional table finishes to a "like new" condition; restoration or replacement of all brass railings; replacement of all wall sconce lighting. The lobby area must create a comfortable, secure and socially oriented atmosphere. Selected furnishings and finishes must enhance the overall décor in order to give the hotel the feel of casual elegance associated with quality upscale hotels. Submit architectural drawings, design specifications, color boards/renderings, to DoubleTree for review, comment, and approval prior to commencing work.	12 Months
19		Lobby - Replace the vinyl wall covering at the lobby level elevator landing (mismatched repairs).	12 Months
20		Registration Desk - Replace the registration desk. Provide a minimum of three registration workstations (based upon the number of guestrooms - 226). Workstations must be grouped together into units to allow circulation around each side of the unit. No more than two workstations are allowed within a single front desk unit. The front desk unit exterior finish must be natural wood, porcelain tile, marble, granite or decorative metal. Wood, wood edged, or laminate writing surfaces are not allowed.	12 Months
21		Registration Desk - Replace the wall treatment on the wall behind the registration desk. Install new wall covering or approved decorative wall treatment. Provide new, illuminated artwork. The use of cabinetry behind the front desk unit is not allowed.	12 Months
22		Registration Desk - Remove the mirrored wall panels across from the registration desk. Install new, updated wall finishes.	12 Months
<b>Business Center</b>			
23		Business Center - Restore all scarred wood cabinetry and counters to a "like new" condition. Install a cord management system to better conceal cords/cables from guest view.	12 Months
<b>Retail Shop</b>			
24		Gift Shop - Replace the carpet and carpet pad (worn). Install new carpet and carpet pad, porcelain tile (18"/45 cm minimum; rectangular shaped tiles permitted), natural stone, or approved alternative decorative hard surface flooring. Install new 6"/1.50 mm wood, tile, approved synthetic, or natural stone base.	12 Months
25		Gift Shop - Replace all laminate display cabinetry; display wall panels and the transaction counter. Install new, furniture quality cabinetry and approved countertops.	12 Months
<b>Public Restrooms</b>			
26		Public Restrooms (Bosanko/Marina) - A complete renovation of the public restroom is required. Renovation must include: replacement of the vinyl flooring with new porcelain tile (18"/45 cm minimum; rectangular shaped tiles permitted) or natural stone tile flooring and matching base; replacement of the vinyl wall covering; new ceiling finishes; replacement of the vanity (vanity skirt must conceal all under-counter plumbing, etc.); installation of a new under-mount sink; new touch-less electronic faucet; new automatic soap dispenser at the vanity bowl (reservoir must be below the counter and spout must extend beyond the edge of the vanity bowl); new automatic paper towel dispenser; a free-standing decorative trash receptacle; installation of artwork; installation of a baby changing station. The ceiling must be constructed of painted gypsum board. Acoustic tile ceiling is allowed, but must not exceed 30% of the total ceiling area. Acoustic ceiling tile must be 2'-0"/60 cm x 2'-0"/60 cm premium tile with regular (reveal) edges.	12 Months
27		Public Restrooms (Fitness Center) - A renovation of the public restrooms is required. Renovation must include: replacement of the vinyl wall covering (visible patches); new touch-less electronic faucet; new automatic soap dispenser; removal of the recessed paper towel dispensers/trash receptacles and the installation of automated touch-less paper towel dispensers and free-standing decorative trash receptacles; installation of artwork; installation of a baby changing station; installation of a new, decorative lighting fixture (to include the fixture in the hall outside of the restrooms).	12 Months
28		Public Restrooms (Madeo Ballroom) - Renovate the restrooms to include: removal of the deadbolt at the entry doors (must not be operable from inside the restrooms); replacement of all stained/discolored ceiling tiles; replacement of all cracked lighting sconce lens covers; removal of the recessed paper towel dispensers/trash receptacles and install new automatic paper towel dispensers and free-standing decorative trash receptacles; installation of artwork within the restroom spaces and a decorative full length mirror near the entries; installation of a baby changing station in each restroom.	12 Months

## EXHIBIT A

29		Public Restrooms (Pool) - A complete renovation of the pool restrooms is required. Renovation must include: replacement of the existing floor tile with new porcelain tile (18"/45 cm minimum; rectangular shaped tiles permitted) or natural stone tile flooring and matching base; replacement of the vinyl wall covering; replacement of all wall tile with new 12"/30 cm minimum tile to coordinate with the new floor tile; new touch-less electronic faucets; new automatic soap dispensers; installation of protective pipe wrap at all exposed vanity plumbing (missing in men's room); removal of the recessed paper towel dispensers/trash receptacles and the installation of automated touch-less paper towel dispensers and free-standing decorative trash receptacles; replacement of the toilet partitions and urinal partitions; installation of automatic flush valves at all toilets and urinals; installation of new artwork; installation of a baby changing station; installation of a new, decorative lighting fixtures.	12 Months
30		Public Restrooms (Terrasinu) - A complete renovation of the public restroom is required. Renovation must include: replacement of the existing floor tile with new porcelain tile (18"/45 cm minimum; rectangular shaped tiles permitted) or natural stone tile flooring and matching base; replacement of the vinyl wall covering; replacement of all wall tile with new 12"/30 cm minimum tile to coordinate with the new floor tile; replacement of the vanity top and the installation of a new under-mount sink; new touch-less electronic faucet; new automatic soap dispenser at the vanity bowl (reservoir must be below the counter and spout must extend beyond the edge of the vanity bowl); new automatic paper towel dispenser; a free-standing decorative trash receptacle; installation of artwork; installation of a baby changing station; installation of a new, decorative lighting fixture; installation of a new exhaust fan (existing fan very noisy).	12 Months
31		Public Restrooms (Lobby Area) - A complete renovation of the lobby public restrooms is required. Renovation must include: replacement of all floor tile with new porcelain tile (18"/45 cm minimum; rectangular shaped tiles permitted) or natural stone tile and matching base; replacement of the vinyl wall covering; replacement of all wall tile with new 12"/30 cm minimum tile to coordinate with the new floor tile; replacement of the vanities; new touch-less electronic faucets; removal of the recessed paper towel dispensers/trash receptacles and the installation of automated touch-less paper towel dispensers and free-standing decorative trash receptacles; installation of new frameless and backlit or decoratively framed vanity mirrors; replacement of the vanity wall sconces with new, decorative fixtures; replacement of the toilet partitions and urinal partitions; installation of automatic flush valves at all toilets and urinals; installation of artwork; installation of a decorative full-length mirror near the entries; installation of a baby changing station; removal of the light switches and the installation of keyed switches or motion sensors.	12 Months

### Food and Beverage Facilities

#	Active Date	Scope of Work	Finish Date
<b>Lounge Facilities</b>			
32		Lounge/Bar - A complete renovation of the bar/lounge is required. The renovation must include: the replacement of all existing carpet and carpet pad and the installation of new carpet, tile, natural stone, wood or other approved flooring; replacement of all pink stone base, trim and low wall caps; replacement of all barstools and wicker seating (existing banquet seating is acceptable); the installation of additional seating (seating count must equal 25% of the hotel key count); replacement of the lighting fixtures over the back bar and all wall sconces. The furnishings, finishes and lighting must provide a visually upscale and contemporary image. Submit all architectural plans, cuisine concept, design specifications and color boards, etc. to Hilton Worldwide for review, comments and approval.	12 Months
33		Lounge/Bar - Restore the worn finish of the bar front to a "like new" condition. Replace the back bar cabinetry. Install new cabinetry to coordinate with the bar front.	12 Months
34		Lounge/Bar - Provide a minimum of two (2) remote controlled, wall mounted flat panel televisions (42"/1.07 m minimum) at the bar area. They must be incorporated into the bar millwork, close to the ceiling, and have all power and cable cords concealed.	12 Months
35		Lounge/Bar - Restore the scarred wood finish of the pool table to a "like new" condition.	12 Months
<b>Restaurant Facilities</b>			

## EXHIBIT A

36		Restaurant - A renovation of the restaurant is required. The renovation must include: the replacement of all existing carpet/carpet pad and tile and the installation of new carpet, tile, natural stone, wood or other approved flooring; replacement of all pink stone base, trim and low wall caps; the reupholstering of all dining chair fabrics; restoration of the wood finishes of all dining chairs to a "like new" condition (finish should closely match the table finish); installation of additional dining chairs and tables (seating count must equal 40% of the hotel key count); new buffets; new ceiling mounted lighting and sconces; replacement of the tile flooring at the server station; repair and repainting of all service station cabinetry. The interior decor of the restaurant shall create an environment traditionally associated with a top quality restaurant. Submit all architectural plans, cuisine concept, design specifications and color boards, etc. to Hilton Worldwide for review, comments and approval.	12 Months
37		Restaurant - Replace the clay tiles at the patio area (cracking, edge tiles missing; noticeable repair work). Install a new, approved flooring material.	12 Months
38		Restaurant - Repair and repaint all rusted railings at the patio area (to include the mesh gate).	12 Months
<b>Kitchens</b>			
39		Kitchen - (Madedo Ballroom) - Replace the cracked tile flooring in the lower and upper level kitchens (to include the tile behind the bar). Repair and repaint the walls at the upper level prep kitchen and replace all missing ceiling tiles.	12 Months
40		Kitchen - (Main) - Replace the tile flooring in the main kitchen (worn; cracked). Repair all damaged FRP wall treatment.	12 Months
41		Kitchen - (Main/Madedo Ballroom) - Install protective pipe wrap at all exposed hand sink plumbing.	12 Months
42		Kitchen (Terrasini) - Restore the painted finish of the prep kitchen flooring to a "like new" condition (worn/chipped).	12 Months
<b>Meeting Spaces</b>			
#	Active Date	Scope of Work	Finish Date
<b>General</b>			
43		Ballrooms/Meeting Rooms/Boardrooms - The primary entrance to the meeting facilities must have a digital, wall mounted event board. All meeting spaces must have electronic signage with the function room name and an integrated LCD display for information services.	24 Months
44		Ballrooms/Meeting Rooms/Boardrooms - Restore all entry and service area doors and door frames to a "like new" condition. Replace all worn/scarred door hardware.	24 Months
45		Ballrooms/Meeting Rooms/Boardrooms - Provide updated lighting controls in all meeting spaces per current DoubleTree by Hilton standards (electronic preset dimmer controls, etc.).	24 Months
<b>Ballrooms</b>			
46		Ballroom (Madedo) - Replace the carpet and carpet pad in the lower and upper levels of the Madedo Ballroom. Install new 6"/150 mm wood or natural stone base.	24 Months
47		Ballroom (Madedo) - Replace the tile flooring at the lower level of the Madedo Ballroom. Install new approved tile and matching base.	24 Months
48		Ballroom (Madedo) - Install vinyl wall covering at the lower level ballroom and stairwell (walls currently painted).	24 Months
49		Ballroom (Madedo) - Replace the stack chair seating (worn; torn). Seating must be stack type chairs or better, with padded seats and backs upholstered with commercial fabric. Chairs must have a flex back and stacking bars. Chair seat must be a minimum of 16"/40 cm wide x 22"/56 cm.	24 Months
50		Ballroom (Madedo) - Replace all window treatments in the lower and upper levels of the Madedo Ballroom. Install new window treatments meeting current DoubleTree by Hilton standards.	24 Months
51		Ballroom (Madedo) - Remove or replace the seating in the Madedo courtyard.	24 Months
52		Ballroom (Madedo) - Replace all chandeliers at the lower and upper levels (to include the bar area). Install new, updated, decorative lighting fixtures.	24 Months
53		Ballroom (Madedo) - Re-face the existing bar front. The bar front finish must be wood, tile, stone or other approved material. Restore all back-bar cabinetry to a "like new" condition. Replace the worn/tarnished foot rest. Bar counter footrests are to be brass, stainless steel, bronze, or equal quality material compatible with the interior design.	24 Months

## EXHIBIT A

54		Ballroom (Macedo) - Remove all mirrored wall panels from the back bar and bar area columns. Install approved, updated finishes.	24 Months
55		Ballroom (Macedo) - Repair and repaint all scarred walls in the lower level of the Macedo Ballroom.	24 Months
56		Ballroom (Macedo) - Replace all damaged/bubbled window tinting at the south facing windows.	24 Months
57		Ballroom (Macedo) - Replace all bar stools at the lower level bar area (finishes mismatched; scarred).	24 Months
<b>Meeting Room Pre-function</b>			
58		Meeting Room Pre-Function (Lobby Area) - Remove the phone bank and repair the walls to a "like new" condition. Install house phones in the lobby soft seating areas as required in the brand standards.	24 Months
59		Meeting Room Pre-Function (Lobby Area) - Install the ATM within a furniture grade decorative cabinet.	24 Months
60		Meeting Room Pre-Function (Lobby Area) - Replace all mismatched ceiling tiles in the exit corridor next to the computer room. Replace the ceiling mounted lighting with new, updated fixtures (lens covers missing).	24 Months
61		Meeting Room Pre-Function (Bosanko/Marina) - Install new and additional soft seating groupings to serve as break out space. Restore the scarred wood finish of the console table to a "like new" condition.	24 Months
62		Meeting Room Pre-Function (Bosanko/Marina) - Repair all damaged and chipped laminate cabinetry in the service area/kitchen (doors misaligned; laminate chipped). Replace all stained and missing ceiling tiles.	24 Months
63		Meeting Room Pre-Function (Bosanko/Marina) - Replace all stained, discolored and/or mismatched ceiling tiles.	24 Months
64		Meeting Room Pre-Function (Bosanko/Marina) - Replace all stained/discolored and missing ceiling tiles within the service area/kitchen and adjacent storage room.	24 Months
<b>Meeting Rooms</b>			
65		Meeting Rooms (Santa Rosa/Portofino/Catalina) - Replace the carpet and carpet pad (worn). Restore all wood base and millwork to a "like new" condition.	24 Months
66		Meeting Rooms (Terrasini) - Professionally clean the carpet to remove all stains and discolorations. If stains cannot be removed, replacement will be required. Install new 6"/1.50 mm wood or natural stone base.	24 Months
67		Meeting Rooms (Marina) - Replace the carpet and carpet pad. Install new carpet to match that in the Bosanko Room.	24 Months
68		Meeting Rooms (Marina) - Replace the vinyl wall covering. Install new vinyl wall covering to match that in the Bosanko Room.	24 Months
69		Meeting Rooms (All) - Restore the wood finishes of all lecterns to a "like new" condition.	24 Months
70		Meeting Rooms (Marina) - Restore all tarnished brass handrails to a "like new" condition. Tighten the loose freestanding railing.	24 Months
71		Meeting Rooms (All) - Replace the worn/discolored stack chair seating. Seating must be stack type chairs or better, with padded seats and backs upholstered with commercial fabric. Chairs must have a flex back and stacking bars. Chair seat must be a minimum of 16"/40 cm wide x 22"/56 cm.	24 Months
72		Meeting Rooms (Portofino) - Replace the patio furnishings (painted finish chipped flaking on tables and chairs).	24 Months
73		Meeting Rooms (Portofino) - Restore the scarred closet doors to a "like new" condition. Replace the missing door hardware.	24 Months
74		Meeting Rooms (Santa Rosa/Portofino/Catalina) - Remove the plate glass mirrors at the service counters. Repair the walls to a "like new" condition. Install artwork or a framed mirror.	24 Months
75		Meeting Rooms (Santa Rosa/Portofino/Catalina/Terrasini) - Replace the window treatments. Install new window treatments meeting all current DoubleTree by Hilton standards.	24 Months
76		Meeting Rooms (Bosanko/Marina) - Replace the roller shade window treatments. Install new window treatments meeting all current DoubleTree by Hilton standards.	24 Months
77		Meeting Rooms (Portofino) - Replace the light lens covers and framework at the ceiling perimeter lighting. Install new, updated lens covers or remove the recessed lighting and install new can lighting.	24 Months
78		Meeting Rooms (Santa Rosa/Portofino/Catalina) - Remove all track lighting. Install new, updated lighting fixtures.	24 Months

## EXHIBIT A

79		Meeting Rooms (Bosanko/Marina) - Install a tamper-proof one-way viewer looking into the function space at the entrance doors. Viewers must be mounted 5'-0" x 1.5 m above the finished floor.	24 Months
80		Meeting Rooms (Portofino) - Repair and repaint all rusted railings at the patio area. Badly rusted railings will require replacement.	24 Months
81		Meeting Rooms (Terrasini) - Remove the curtain wall concealing the meeting room storage area from the main meeting area. Construct a permanent storage room.	24 Months
82		Meeting Rooms (Terrasini) - Replace all stained/discolored, mismatched and/or missing ceiling tiles in the meeting room and storage room.	24 Months
<b>Board Rooms</b>			
83		Boardrooms - Replace the carpet and carpet pad. Restore all scarred wood base and chair/presentation rail to a "like new" condition.	24 Months
84		Boardrooms - Replace the boardroom tables. Provide a permanent conference table, seating a minimum of twelve people, with wood or stone table surfaces and edges. Glass or lacquer finish is not acceptable. Wood conference tables must be finished with a high-grade polyurethane finish. Power and data outlets must be integrated into the table top with all power cords, etc. completely concealed to a floor outlet.	24 Months
85		Boardrooms - Replace the window treatments. Install new window treatments meeting all current DoubleTree by Hilton standards.	24 Months
86		Boardrooms - Remove the plate glass mirrors at the service counter in Boardroom A. Repair the walls to a "like new" condition.	24 Months
87		Boardrooms - Install a minimum 52"/1.3 m wall mounted LCD television with connectivity to the MATV system and to a boardroom table connection.	24 Months
88		Boardrooms - Remove the existing projection screens.	24 Months
89		Boardrooms - Remove all track lighting. Install new, updated lighting fixtures.	24 Months
<b>Recreational Areas</b>			
#	Active Date	Scope of Work	Finish Date
<b>Fitness Center</b>			
90		Fitness Center - Replace the existing flooring. Install the brand approved ECOmax modular floor tiles throughout the fitness center and Expona wood-look flooring at the entry. Replace the cove base. Install new approved wood substitute base or better.	12 Months
91		Fitness Center - Remove the vinyl wall covering (scarred). Install approved wall finishes throughout the fitness center space (painted neutral and accent wall colors).	12 Months
92		Fitness Center - Install the required inflatable balance ball.	12 Months
93		Fitness Center - Restore the wood finish of the towel station to a "like new" condition.	12 Months
94		Fitness Center - Replace all damaged control buttons on the cardio equipment (incline, speed, etc.).	12 Months
95		Fitness Center - Conceal all cables/cords from guest view (cable by the treadmill is running from the ceiling to the cord management system).	12 Months
96		Fitness Center - Replace the light switches. Lights must be wired so as to remain on at all times or have a keyed switch.	12 Months
97		Fitness Center - Replace all damaged ceiling grid and all stained/discolored ceiling tiles.	12 Months
<b>Pool Area</b>			
98		Pool Area - Repair all cracks in the pool/whirlpool deck and restore the decorative treatment to a "like new" condition (faded in areas).	12 Months
99		Pool Area - Replace the pool and whirlpool coping (cracked in many areas).	12 Months
100		Pool Area - Replace all pool furniture (teak and metal furniture). Provide chaise lounges, tables and seating to accommodate a minimum of 20 people in the pool area. Chaise lounges and chairs must be sling back type; plastic straps must not be used. A minimum of three tables with umbrellas are required.	12 Months
101		Pool Area - Replace all damaged/cracked tile water depth and "No Diving" markings at the pool coping. Install "No Diving" markings adjacent to the depth markings on the inside rim of the pool perimeter. Lettering must be 4" x 10.2 cm high. Painted, stenciled, and vinyl appliqué lettering is not allowed.	12 Months

## EXHIBIT A

102		Pool Area - Replace the faded depth markings inside the whirlpool. Install hard tile water depth and "No Diving" markings in contrasting colors on the top of the whirlpool coping and on the inside rim of the whirlpool perimeter. Lettering must be 4"/10.2 cm high. Painted, stenciled, and vinyl appliqué lettering is not allowed.	12 Months
103		Pool Area - Replace all older (faded green) signage at the restrooms and building entrance.	12 Months
<b>Other Recreational</b>			
104		Tennis Courts - Repair and repaint all scorred, flaking and worn areas of the chain link fencing. Repair the damaged/flaking areas of the tennis court surface.	12 Months
105		Tennis Courts - Replace all damaged/torn wind screens.	12 Months
<b>Back of House</b>			
<b>#</b>	<b>Active Date</b>	<b>Scope of Work</b>	<b>Finish Date</b>
<b>General</b>			
106		General - Install protective shields, lens covers, or diffusers at all light fixtures (recessed and surface mounted) in back-of-house and public areas.	12 Months
<b>Employee Break Room</b>			
107		Employee Breakroom - Install a counter and cabinets to house the microwave, a coffee maker, a full size refrigerator, a two-compartment stainless steel sink and filtered water.	12 Months
108		Employee Breakroom - Replace the worn seating.	12 Months
<b>Employee Restroom/Showers/Lockers</b>			
109		Employee Restrooms - Replace the missing light shade in the men's restroom.	12 Months
<b>Offices</b>			
110		Administrative Offices (Food & Beverage) - Replace the carpet and carpet pad. Replace all stained, discolored or sagging ceiling tiles.	12 Months
111		Administrative Offices (Registration Area/Sales & Catering/Food & Beverage/Engineering) - Remove the mini-blinds at all exterior windows. Install two-inch wood blinds.	12 Months
112		Administrative Offices (PBX Room) - Replace the carpet.	12 Months
113		Administrative Offices (Sales & Catering) - Replace the worn entry door hardware.	12 Months
<b>Main Laundry</b>			
114		Laundry - Replace all damaged and/or missing vinyl tile flooring. Repair and repaint all damaged walls.	12 Months
<b>Service Corridors</b>			
115		Service Corridors - Replace the damaged vinyl tile flooring between the kitchen and laundry areas (near the ice machine).	18 Months
116		Service Corridors - Restore the painted flooring at the service elevator landings (chipped, pitted).	18 Months
<b>Guest Support</b>			
<b>#</b>	<b>Active Date</b>	<b>Scope of Work</b>	<b>Finish Date</b>
<b>Vending</b>			
117		Vending Areas - Remove the old door frames and install cased openings at all vending areas.	18 Months
118		Vending Areas - Replace the ceiling mounted lighting. Install new, updated decorative lighting fixtures.	18 Months
<b>Circulation Areas</b>			
<b>#</b>	<b>Active Date</b>	<b>Scope of Work</b>	<b>Finish Date</b>

Corridors			
119		Corridors - Replace the carpet and carpet pad (to include the lobby stair and stairwell #2). Install new 4"/100 mm wood or approved synthetic base.	18 Months
120		Corridors - Replace the vinyl wall covering. Install new full height corner guards on all outside corners in the corridors. The corner guards shall be colored opaque plastic to match the wall color and must be adhesive mounted. Clear or screw attached corner guards are not acceptable. Corner guard flanges must be a maximum width of 1"/25 mm.	18 Months
121		Corridors - Install new DoubleTree Hilton approved window treatments at all corridor windows.	18 Months
122		Corridors - Install artwork positioned appropriately down the corridor. Artwork should be of a nature that reflects the geographic area or local artists.	18 Months
123		Corridors - Replace all cracked wall sconce lens covers. If matching lens covers cannot be found, replacement of the wall sconces will be required.	18 Months
124		Corridors - Repair all damaged/chipped laminate at the guestroom entry and service area/fire doors.	18 Months
125		Corridors - Repair and repaint all damaged areas of the corridor ceilings to a "like new" condition (many visible patches from high-speed internet installation).	18 Months
Elevator Lobbies			
126		Elevator Lobbies - Install a new seating group and console table at each elevator landing. Provide a house phone. Console table must conceal all telephone and/or lamp cords. Install new artwork or mirror above the console table. Provide a decorative trash urn.	18 Months
Elevators			
127		Elevators (Guest Tower) - A renovation of the elevator is required. Renovation must include: restoration of the floor tile grout to a "like new" condition; new decorative ceiling panels and lighting (egg-crate lighting not allowed). All controls, signals and stainless steel doors are to be in "like new" condition.	18 Months
128		Elevators (Macedo Ballroom) - A complete renovation of the elevator is required. Renovation must include: removal of the vinyl tile flooring and the installation of new natural stone or other approved decorative hard surface flooring; restoration of all interior wall panels; restoration of all brass handrails; new decorative ceiling panels and lighting (egg-crate lighting not allowed). All controls, signals and stainless steel doors are to be in "like new" condition or replaced.	18 Months
129		Elevators - Install "In Case of Fire, Use Stairs..." signage within the elevator cabs. Signage must match the corridor sign package.	18 Months
Stairwells			
130		Stairwells - Repair and repaint all chipped railings in stairwell #2.	18 Months
131		Stairwells - Repair and repaint all scarred/chipped flooring in stairwells #1, #3 and #4.	18 Months
132		Stairwells - Replace the ceiling mounted lighting in stairwell #2. Install new, updated decorative lighting fixtures.	18 Months
Guest Rooms			
#	Active Date	Scope of Work	Finish Date
Guest Rooms			
133		Guestrooms - A complete renovation of all guestroom and parlor area soft goods is required. Renovation must include: replacement of carpet and carpet pad (a natural stone or quartz composite threshold is required at entry, bath, and connecting doors); installation of new carpet, wood or approved alternative base; refinishing of all case good pieces to a "like new" condition; replacement of all soft seating; replacement of all desk chairs; replacement of all dining chairs; replacement of all window treatments (fabric valances or cornices are not allowed - an architectural detail such as a window pocket, soffit, crown molding, etc., which conceals the drapery hardware is required).	18 Months
134		Guestrooms - Replace all worn/tamished auxiliary door lock/latches at guestroom and connecting doors. Ensure that lever handle door hardware is installed at all connecting doors (e.g. room #257). Ensure that all hardware is of the same finish (some mismatched).	18 Months
135		Guestrooms - Replace the existing mirrored closet doors. Install new standard swing doors. Mirrored, bi-fold, bypass, and fabric type folding (accordion) doors are not acceptable.	18 Months

Page: (11 of 13)

## EXHIBIT A

136	Guestrooms - Install a full length mirror with a minimum exposed glass measurement of at least 15"/37.5 cm wide and 60"/1.5 m high. Mirror must be located near the dressing area or closet. A mirror mounted on the back of the bathroom or closet door is acceptable. If wall-mounted, the mirror must be framed.	18 Months
137	Guestrooms - Replace all white appliances at wet bars in suites. All appliances must be black or stainless steel in color. Replace all acrylic knobbed faucets with new single or dual lever-handled faucets.	18 Months
138	Guestrooms - Provide a dedicated area for coffee/tea service outside of the bathroom. Provide one of the following options for the proper presentation of the coffee maker and coffee accessories: a) A minimum 66"/1.68 m wide television chest for the coffee service to be placed next to the LCD television b) A dedicated, pull out, water tight drawer in the television chest with accessible power c) A separate location with a wet bar area and counter space with accessible power d) If a mini bar or refrigerator are encased in a separate case good, the coffee service can be placed on top.	18 Months
139	Guestrooms - Install the DoubleTree by Hilton "Sweet Dreams" bedding program in all guestrooms and suites. This bedding program includes: jumbo down pillows (4 per full/queen bed and 5 per king bed) with each pillow stacked upright against the headboard; one (1) "Sweet Dreams" signature euro-style pillow with embroidered pillow case presented in front of jumbo down pillows; a "Super Topper" mattress pad. For the top of the bed, hotels must provide either: * A white duvet cover with a "fully washable" decorative runner (22" wide) at the foot of the bed * or, triple sheeting with Down Dreams comforter inserted within the triple sheeting and a "fully washable" separate double-sided decorative scarf (22" wide). See DoubleTree by Hilton Brand Management for specifications and ordering requirements for the "Sweet Dreams" bedding program. The "Sweet Dreams" bed experience is a proprietary product and must be directly ordered from or sourced through Hilton Supply Management.	18 Months
140	Guestrooms - Replace the light switch. Install an illuminated wall switch immediately adjacent to the entrance door.	18 Months
141	Guestrooms - Replace the nightstand lamps. One non-switched duplex outlet is required at each bedside surface. Light fixtures with outlets in the base satisfy this requirement. Outlets are not allowed in wall-hung light fixtures at the bedside surface.	18 Months
142	Guestrooms - Replace all older (Mitsubishi) HVAC units in the guestrooms. Install units equivalent to the newer Samsung units (digital thermostats, etc.).	18 Months
143	Guestrooms - Install a battery powered safe in all guestrooms. Specifications can be found in the DoubleTree by Hilton Operations Standards.	18 Months
144	Guestrooms - Replace all guestroom patio seating. Install new sling-type seating.	18 Months
<b>Guest Bathrooms</b>		
145	Guest Bathrooms - A complete renovation of the guest bathrooms is required. Renovation must include: restoration of all entry doors to a "like new" condition and replacement of all worn door hardware; installation of new floor tile (16 /40 cm x 16 /40 cm or 12 /30.5 cm x 18 /45 cm minimum) and matching base; replacement of the vinyl wall covering; replacement of the vanity tops and the installation of new vanity bases; replacement of the vanity mirrors; installation of new decorative lighting fixtures at the vanity; installation of a vapor-resistant ceiling mounted lighting fixture over the tub/shower area; replacement of the tub surrounds (12 /30 cm x 12 /30 cm minimum; rectangular shaped tiles allowed); replacement of all vanity and tub chrome; refinishing of tub bottoms using an approved vendor and process; installation of artwork above the toilet.	18 Months
146	Guest Bathrooms - In King bedded guestrooms a shower in lieu of a combination bathtub/shower is required. Remove the existing tub/shower unit and surrounds and construct new shower stalls. Shower enclosures must be frameless clear glass with a frameless hinged door, or a 3/8"/9.5 mm clear glass, frameless bypass shower door approved by Hilton Worldwide. Locate glazing flush with outside face of shower pan curb. Doors must be 74"/1.88 m high minimum. Install a soap dish in the corner on the showerhead wall 48"/1.2 m above the finished floor. Install a footrest in the corner opposite the showerhead on the back wall 15"/38 cm above the finished floor.	18 Months
147	Guest Bathrooms - Install two soap dishes in all bathtub/shower combos. Soap dishes must not have grab handles and must not be metal or plastic. A soap dish must be placed in the corner on the showerhead wall, 48"/1.2 m above the finished floor, with a bathtub height soap dish centered on the back wall 24"/61 cm above the finished floor. Bathtubs or showers with multiple grab bars required by the local jurisdiction may adjust soap dish locations as needed.	18 Months

148	Guest Bathrooms - A grab bar is required in all bathtub/shower combos and in all shower stalls. A decorative chrome or stainless steel grab bar 24"/60 cm in length must be installed vertically on the bathtub wall, 21"/52.5 cm from the showerhead wall at bathtubs and 13"/33 cm from the showerhead wall at showers, with the bottom flange of the grab bar 30"/76 cm above the finished floor.	18 Months
149	Guest Bathrooms - In accessible guestroom baths, install a typical guest bathroom shower head at the standard height (installed in some, but not all accessible rooms). Additionally, install a diverter valve and an additional bathtub/shower showerhead on a flexible hose mounted on a chrome riser permitting height adjustments from 42"/1.07 m - 72"/1.83 m above the finished floor.	18 Months
150	Guest Bathrooms - Remove the towel racks from above the toilet. Towel storage must be incorporated into the vanity area to accommodate the brand terry program. Towels must not be stored over the water closet or in the bathtub/shower area.	18 Months
151	Guest Bathrooms - Replace the existing vanities. Install new vanity bases with a decorative/case good appearance and a drawer or cubby for hair dryer storage. Towel storage must also be incorporated into the vanity area to accommodate the brand terry program. Towels must not be stored over the water closet or in the bathtub/shower area. Vanity tops must be a minimum 3/4"/19 mm thick granite, stone, glass (semi-frosted underneath), or approved alternative and be stain resistant. All tops must have a 4"/100 mm backplash.	18 Months
152	Guest Bathrooms - An 18"/45 cm towel bar or 6"/150 mm towel ring must be installed immediately adjacent to the vanity. Towel bar/ring is not allowed over the water closet. The towel bar may be mounted on the face of the vanity.	18 Months

The improvements identified in this property improvement plan ("PIP") relevant to the brand specified on the cover page of this PIP ("Brand") are based on conditions at the hotel existing on the Inspection Date specified on the cover page of this PIP ("Inspection Date"). This PIP and any specified waivers of relevant brand standards are only effective for the purpose of incorporation by reference into a fully executed and dated agreement relating to the implementation of the PIP ("Relevant Agreement") with the affiliate entity of Hilton Worldwide, Inc. that is party to such Relevant Agreement ("Hilton"), if such Relevant Agreement is entered into within 180 calendar days of the Inspection Date. In the event that a Relevant Agreement is not entered into within 180 calendar days of the Inspection Date, an updated PIP may be required (in Hilton's absolute discretion). The preparation and/or supply of this PIP shall not obligate Hilton (or any affiliate of Hilton) to enter into any Relevant Agreement (including, but not limited to, a franchise agreement or a management agreement).

This PIP review is limited to aesthetic and functional layout and design, and certain functional, operational and quality criteria as specified by Hilton. It does not encompass, and Hilton does not make any representation or warranty as to, nor shall Hilton be responsible for, the architectural, structural, mechanical, or electrical adequacy, accessibility requirements or other compliance with applicable government or other legal requirements. Compliance is required with brand standards (including the fire safety and security equipment standards specified by Hilton), all applicable local, state and federal building codes, any legally mandated accessibility requirements and all other legal requirements. Accordingly, Hilton recommends that its counterparty(ies) engage an appropriate professional team and legal counsel to advise on such compliance. Any omission in this PIP report does not constitute a waiver of such requirements and does not release any obligation in any Relevant Agreement to conform to brand standards. Nothing in this PIP is intended to modify the terms of any Relevant Agreement to which it may be attached and/or incorporated by reference. In the event of any conflict of the terms, the terms of the Relevant Agreement are the terms that prevail.

The works set out in this PIP are required to be completed by the specified "Finish Date". All "Finish Dates" that are a specified number of months or days shall mean the number of months or days from the date of the Relevant Agreement into which the PIP is incorporated by reference.